



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-15-00448

OWNER'S NAME: SHCHEDRIN

DATE: 7/22/2016

TYPE: Framing

TIME STARTED: 10:15 AM

INSPECTOR: Jessica Contratto

MAP NUMBER: 22-11-15051-0007

1. Mechanical and plumbing inspection performed
2. Plumbing roughed in. Not on test
3. Mechanical rough in ok
4. Heat duct in garage must be removed. Unit supplying heat to residence cannot heat garage area. Garage can be heated with electric wall heat or gas powered unit heater if desired
5. Vented windows installed
6. Gas line not installed yet. Must be at 15# minimum for test
7. Electrical not installed yet. Complete electrical and L&I inspection
8. Can lights or other penetrations not allowed in garage ceiling fire separation unless 1 hr fire rated
9. Repair dryer vent where broken on garage level
10. Tempered window required at stair landing or guard must be installed over portion above landing area. Window above 36" from landing not required to be tempered

INSTRUCTIONS: Complete electrical and gas pipe installation. Wood stove will need to be seen before cover. Fresh air to firebox required on installation

NEXT INSPECTION: Plumb/frame

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL
ADDRESS: _____ [jessica.contratto @co.kittitas.wa.us](mailto:jessica.contratto@co.kittitas.wa.us)

INSPECTION REQUEST LINE: 509-962-7694

<http://www.co.kittitas.wa.us/cds/building/inspection-request.aspx>

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506