



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

## INSPECTION REPORT

PERMIT NUMBER: BP-15-00492 OWNER'S NAME: MERITAGE  
DATE: 1/20/2016 TYPE: Framing  
TIME STARTED: 11:27 AM INSPECTOR: Jessica Contratto  
MAP NUMBER: 20-15-20058-0016

	1. Move lineset away from B-vent in attic area
	2. Heat trunk above bed 3 not screwed/sealed at elbow
	3. H1 clips on trusses
	4. Girder truss C04- strap down both ends. Strap to top plate at bed 3 end
	5. Post down under girder truss at master bath toilet room header
	6. Insulation shield at water heater b-vent in attic
	7. Properly apply mastic to proper thickness to seal ductwork

INSTRUCTIONS: complete above, ok to insulate. Spray foam areas where proper venting cannot be achieved

NEXT INSPECTION: insulation

RE-INSPECTION FEE DUE? ☒ NO ☐ YES \$ \_\_\_\_\_

**IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION**

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL ADDRESS:

\_\_\_\_\_ [jessica.contratto@co.kittitas.wa.us](mailto:jessica.contratto@co.kittitas.wa.us)

• INSPECTION REQUEST LINE: [www.co.kittitas.wa.us/cds/request.asp](http://www.co.kittitas.wa.us/cds/request.asp) or 509-962-7694 •  
411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506