



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-15-00554

OWNER'S NAME: HABERMAN

DATE: 10/27/2015

TYPE: Framing

TIME STARTED: 10:36 AM

INSPECTOR: Jessica Contratto

MAP NUMBER: 20-16-27050-0002

	1. Shear also inspected
	2. Front of garage not per detail 5/D1. Header required to extend over shearwalls at
	garage door, straps over header, stagger nail sheathing to header 3" oc. All panel edge
	nailing at 3" also
	3. Outlookers not per detail 2/D1. LTP5 clips top plate to truss, outlookers at 24".
	Currently at 48"
	4. stamped truss sheets not on site
	5. Man door added in place of one garage door. Verify installed header is correctly sized
	6. Window placed in back shearwall
	7. Windows omitted on sides-ok

INSTRUCTIONS: complete above or obtain engineer approval or fix. Do not cover

NEXT INSPECTION: re-inspect

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL ADDRESS:

_____ [jessica.contratto @co.kittitas.wa.us](mailto:jessica.contratto@co.kittitas.wa.us)

• INSPECTION REQUEST LINE: www.co.kittitas.wa.us/cds/request.asp or 509-962-7694 •

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506