



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-15-00560

OWNER'S NAME: MYERS

DATE: 4/13/2016

TYPE: Framing

TIME STARTED: 8:53 AM

INSPECTOR: Jeremy Haberman

MAP NUMBER: 17-18-10030-0013

1. Mechanical Corrections OK.
2. Gas Line at 15#/15min. OK.
3. Engineer Stamped Truss Sheets Not On Site. Required for Framing Inspection.
4. Porch Cover Not Built Per Plan. (4)Laminated 2x6 Used Instead of 6x6. 3 1/8"x 13" Glulam used instead of 6x10. Photos On "T" Drive. Plan Reviewers OK required
5. NOTE: Skylight Depicted In Drawing Ommitted.
6. NOTE: Insulation and Vapor Barrier Will Be Required Behind Tub Enclosure at I nsulation Inspection.
7. NOTE: Drawings Do Not Identify Garage Headers or Eve Over Hange Header. Verif ication Required.

INSTRUCTIONS: OK to Insulate. Corrections Must Be Complete Prior to Insulation Inspection.

NEXT INSPECTION: Insulation.

RE-INSPECTION FEE DUE? ☒ NO ☐ YES \$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL
ADDRESS: jeremy.haberman @co.kittitas.wa.us

INSPECTION REQUEST LINE: 509-962-7694

<http://www.co.kittitas.wa.us/cds/building/inspection-request.aspx>

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506