



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-15-00642

OWNER'S NAME: MILLER

DATE: 11/2/2016

TYPE: Framing

TIME STARTED: 2:14 PM

INSPECTOR: Jeremy Haberman

MAP NUMBER: 19-16-06050-0012

1. 2x6 PT Mud Sill Plate Not Bolted Using 3x3 Plate Washer Per Requirement.
2. Shear Nailing From T-111 to PT Sill Plate Must Be Hot Dipped Galvanized.
3. Porch Beam Pocketed Into Wall at Covered Porch Must Have Strap Per Drawing On Top OF Beam.
4. 2x6 Flat Outlookers Must Be Spaced No More Thaan 32" On Center. 48" Spacing Observed.

INSTRUCTIONS: MAke Corrections.

NEXT INSPECTION: Re Inspect

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL
ADDRESS: jeremy.haberman @co.kittitas.wa.us

INSPECTION REQUEST LINE: 509-962-7694

<http://www.co.kittitas.wa.us/cds/building/inspection-request.aspx>

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506