



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-16-00268

OWNER'S NAME: JERRY

DATE: 4/24/2017

TYPE: Framing

TIME STARTED: 10:40 AM

INSPECTOR: Jessica Contratto

MAP NUMBER: 22-11-15052-0014

1. Inspection is for covering front window wall
2. Strap cantilevered beams; over prow wall; to top plate and down to studs
3. Front wall to be SW-4 with 15/32" sheeting, 10d nails at 4", and 3x edge studs
. Currently has 7/16" sheeting. Owner wants to install 2 sided shearwall in this area. Obtain engineer approval and provide letter
4. Complete electrical and have L&I inspect before cover
5. Smoke/CO needed outside master bedroom

INSTRUCTIONS: Complete above

NEXT INSPECTION: Mechanical/plumbing/front wall insulation

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL
ADDRESS: _____ [jessica.contratto @co.kittitas.wa.us](mailto:jessica.contratto@co.kittitas.wa.us)

INSPECTION REQUEST LINE: 509-962-7694

<http://www.co.kittitas.wa.us/cds/building/inspection-request.aspx>

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506