



KITTITAS COUNTY COMMUNITY DEVELOPMENT SERVICES

INSPECTION REPORT

PERMIT NUMBER: BP-16-00651

OWNER'S NAME: TALISMAN

DATE: 3/17/2017

TYPE: Framing

TIME STARTED: 1:57 PM

INSPECTOR: Justin Bennett

MAP NUMBER: 20-15-19056-0006

1. Provide manufacturer approval for sprinkler bored hole in trusses
2. Install 8x8 @ loft beam per A5
3. Install (5) 2x6 @ PL in bedroom 2 - clouded on A5
4. Install web stiffener @ cantilevered floor framing per 9/D2 at entry (A4)
5. Provide strap @ top plate break at steel beam in master bedroom - clouded A3
6. Provide engineer fix for entry and porch posts not resting on piers - multiple locations
7. Provide (4) 2x6 @ stair/kitchen intersection - clouded on A3

INSTRUCTIONS: Complete above/Verify @ insulation

NEXT INSPECTION: Insulation

RE-INSPECTION FEE DUE?



NO



YES

\$ _____

IF REQUIRED, RE-INSPECTION FEES MUST BE PAID PRIOR TO SCHEDULING A RE-INSPECTION

QUESTIONS? PLEASE CONTACT THE INSPECTOR AT THE FOLLOWING E-MAIL
ADDRESS: _____ justin.bennett@co.kittitas.wa.us

INSPECTION REQUEST LINE: 509-962-7694

<http://www.co.kittitas.wa.us/cds/building/inspection-request.aspx>

411 N. Ruby Street, Suite 2, Ellensburg, WA 98926 • Main Office Line: 509-962-7506