

Frosty Pines II Short Plat - File Number SP-24-00008
Condition Compliance Document

Approval Condition	Applicant Response	Staff Review
1. Building		
A. All new construction must meet the International Code requirements.	Noted	
B. Environmental and statutory review may be required for all current and future development, construction, and improvements. The applicant and/or all future owners of any lot or lots within this subdivision are responsible for compliance with all applicable local, state, and federal rules, requirements, codes, and regulations. It is incumbent upon said applicants and future owners to investigate for, and obtain from the appropriate agency or their representative, all required permits, licenses, and approvals for any development, construction, and/or improvements that occur within the boundaries of this subdivision.	Noted	
2. Roads and Transportation		
A. This application is subject to the latest revision of the Kittitas County Road Standards. The following conditions apply and must be completed prior to final approval of this project. A performance guarantee may be used in lieu of the required improvements, per the conditions outlined. (KCC 12.01.150)	Noted	
B. A driveway shall service no more than four tax parcels. See Kittitas County Road Standards.	Noted	
C. New access easements shall be a minimum of 30'. The roadway width shall have a minimum width of 12' if the length of the driveway is less than 150', or 16' if the length of the driveway is more than 150'.	Noted	
D. Driveways longer than 150' in length are required to provide a Fire Apparatus Road Turnaround meeting the requirements of appendix D in the International Fire Code.	Noted	
E. Max grade shall be 10%.	Noted	
F. Crush surface depth per WSDOT Standards.	Noted	
G. Maintenance of driveway approaches shall be the responsibility of the owner whose property they serve. The County will not maintain accesses.	Noted	
H. An approved access permit shall be required from the Department of Public Works prior to creating any new driveway access or performing work within the county road right-of-way.	Noted	
I. Contact the Kittitas County Rural Addressing Coordinator at (509) 962-7523 to obtain addresses prior to obtaining a building permit. A parcel cannot receive a building permit or utilities until such parcel is identified with a 911 address.	Noted	
J. Contact the Kittitas County Fire Marshal regarding any additional access requirements for Emergency Response.	Noted	
K. Mailboxes must be approved by U.S. Postal Service. Mailbox locations are site specific. Contact your local Post Office for location and design standards before beginning construction.	Noted	
L. Except as exempted in Section KCC 14.05.060, no grading or filling upon a site involving more than one hundred (100) cubic yards shall be performed without a grading permit from the County Engineer or Public Works designee (KCC 14.05.050). An application for grading in excess of five hundred (500) cubic yards shall be accompanied by an engineered grading plan (KCC 14.05.080).	Noted	
3. State and Federal		
A. Applicant shall meet all state and federal regulations.	Noted	
4. Survey		
A. The new division line shall have corners set in the field and be shown on the face of the survey.	Completed and shown on survey	
B. The final plat shall show the basis of bearing.	Shown	
5. Plat Notes		
A. The following plat notes shall be recorded on the final mylar drawings:		
• Environmental and statutory review may be required for all current and future development, construction, and improvements. The applicant and/or all future owners of any lot or lots within this subdivision are responsible for compliance with all applicable local, state, and federal rules, requirements, codes, and regulations. It is incumbent upon said applicants and future owners to investigate for, and obtain from the appropriate agency or their representative, all required permits, licenses, and approvals for any development, construction, and/or improvements that occur within the boundaries of this subdivision.	Shown	
• All development shall comply with International Fire Code.	Shown	
• Maintenance of the access is the responsibility of the property owners who benefit from its use.	Shown	
• An approved access permit will be required from the Department of Public Works prior to creating any new driveway access or performing work within the county road right-of-way.	Shown	
• The approval of this division of land provides no guarantee that use of water under the ground water exemption (RCW 90.44.050) for this plat or any portion thereof will not be subject to curtailment by the Department of Ecology or a court of law.	Shown	
• Any further subdivision or lots to be served by proposed access may result in further access requirements. See Kittitas County Road Standards.	Shown	

• Metering is required for all new uses of domestic water for residential well connections and usage must be recorded in a manner consistent with Kittitas County Code Chapter 13.35.027 and Ecology regulations.	Shown	
• The subject property is within or near designated agricultural lands, forest lands, or mineral resource lands on which a variety of commercial activities and mineral operations may occur that are not compatible with residential development for certain periods of limited duration. Commercial natural resource activities and/or mineral operations performed in accordance with County, State and federal laws are not subject to legal action as public nuisances.	Shown	
6. Other		
A. Taxes shall be paid in full on all tax parcels involved in this land use action as required by Washington State Law (RCWs 84.40.042 & 84.56.345) prior to final plat recording.	Completed	
B. Should ground disturbing or other activities related to the proposed subdivision result in the inadvertent discovery of cultural or archaeological materials, work shall be stopped in the immediate area and contact be made with the Washington State Department of Archaeology and Historic Preservation (DAHP) and the Confederated Tribes of the Colville Reservation. Work shall remain suspended until the findings are assessed, and appropriate consultation is conducted. Should human remains be inadvertently discovered, as dictated by Washington State RCW 27.44.055, work shall be immediately halted in the area and contact made with the coroner and local law enforcement in the most expeditious manner possible.	Noted	
C. At least one soil log per lot not already served by an on-site septic must be provided prior to final plat approval	Completed	
D. A signed, notarized and recorded two party shared well user's agreement between lots to be served by the individual well and well log for the existing well must be submitted to the Health Department for review.	Class B Well with one-hook up remaining	
E. A 100 foot protection zone around each existing and proposed well site must be established prior to final plat approval.	Class B well system is operational and in compliance	
F. A Forest Practices Application (FPA) from the DNR shall be obtained if merchantable timber is removed/harvested as part of the proposal and/or is being converted out of forest land (RCW 76.09 and WAC 222).	Noted	
G. Both sheets of the final mylars shall reflect short plat number SP-24-00008 and an accurate legal description shall be shown on the face of the final plat. Engineers and Surveyors need to be cognizant of all the requirements related to Final Plats (KCC 16.20) and Survey Data and Dedications (KCC 16.24). The final plat must be submitted in full conformance with these chapters of Kittitas County Code; non-compliant mylars will be rejected and returned to the applicant. A final plat file number will be assigned when CDS receives your final plat application. This file number will also be required on the face of the final plat.	Waiting on final short plat number	
H. It is the responsibility of the Professional Licensed Surveyor (PLS) to ensure the lot closures are correct and accurate.	Noted \$ PROVIDED	
I. This preliminary approval will expire 5 years from the date of this determination if no extension is filed in accordance with KCC 16.32.090.	Noted	